

Responses to the reviewers

Relative impact of aerosol, soil moisture and orography perturbations on deep convection

by Linda Schneider et al.

June 7, 2019

We thank both reviewers for reading the manuscript and providing detailed comments. We have carefully considered all comments and changed the manuscript accordingly. Please find below our responses in blue.

We also added Andrew I. Barrett to the list of authors, as he contributed with technical implementations to write out microphysical process rates and to use horizontal heterogeneous CCN concentrations in the COSMO model code. In addition, he was involved in the interpretation of the results.

Reviewer 1

General comments:

1. The authors claim to investigate the contribution of soil moisture, aerosols and orography on the predictability of deep convection. Yet, they investigate the impact of these factors on 24-hour sums of precipitation. In order to address predictability, further analysis would be needed, as e.g. the RMSE between the simulations, the growth of the RMSE over time, and the saturation of the error. I suggest removing the term "predictability" from the manuscript. Moreover, the term "ensemble spread" is used. Yet, the different experiments are introduced as "sensitivity studies", but not as "ensemble perturbations".

We agree with the reviewer that an analysis of the RMSE would provide a valuable information to the reader. We therefore made those calculations and inserted a new figure at the end of section 3.1 together with new text.

Changes to paper:

"To further address deviations of the sensitivity runs from the reference run, we now analyze the root mean square error (RMSE) of total precipitation and its temporal evolution (Fig. 6). It can be seen that the increase of errors is generally largest for the times with maximum precipitation rates. For the weak forcing cases (Fig. R.1 (a)-(c)), orography and aerosol modifications lead to larger RMSE values already for smaller rain rates in the early morning hours than the soil moisture runs. Interestingly, the soil moisture runs show a steeper increase once convection is initiated around 10:00–11:00 UTC. In agreement with recent findings of Baur et al. (2018), this indicates that heterogeneous soil moisture perturbations mainly influence the convection initiation via secondary dynamical effects (like thermally induced circulations), whereas CCN and orography variations induce variability already from the beginning of the simulation. Overall, the errors are largest in the soil moisture and orography runs and smallest in the aerosol runs. This is also true for the cases with strong synoptic forcing (Fig. 6 (d)-(f)). However, there is no distinct temporal delay of the soil moisture runs indicating that its influence on precipitation initiation is weaker than on days with weak synoptic forcing. We also find that the spread at the end of the simulation of the aerosol runs is always higher for strong than for weak synoptic forcing, which points to a larger role of CCN concentrations in this weather regime. The same holds true for the soil moisture runs which also possess the largest spreads of all sensitivities studied here. On average, the orography runs have a similar spread in both weather regimes."




Figure R.1: Root mean square error (RMSE) for precipitation of the sensitivity runs compared to the reference run. Thick lines indicate the mean and color-coded areas the range between the minimum and maximum RMSE.

Concerning the terms predictability, ensemble, sensitivity:

This study deals with the predictability of deep convection and explores new techniques to disturb the model. We are aware that the ensemble size is rather small and that the terms predictability and sensitivity have to be chosen with care. We therefore decided to keep the term predictability in the manuscript (5 occurrences in Abstract, Introduction, Summary).

Changes to paper:

Whenever we wrote “our ensemble” in the text, we exchanged it to “sensitivity runs” or “model runs” as the number is too small to be named ensemble.

- Page 4, sensitivity studies: The perturbations of soil moisture are applied to the relative water content `w_so`, irrespective of the soil type. Dependent on the soil type this results in a different perturbation. It would be better to first compute the soil-moisture index/soil moisture range/fraction of available water $(\theta - \theta_{wp}) / (\theta_{fc} - \theta_{wp})$, to then perturb this quantity, and to convert back to relative water content, as this would yield a fairer perturbation across soil types. Is the field capacity reached in the simulations with increased soil water content?

We take the different soil types into account **just by** perturbing the relative water content. The COSMO model uses the volumetric water content. E.g. to get spatial homogeneous soil water content, we need to adjust the volumetric water content in such a way that the relative water content is the same in the entire model domain. The relative water content (RWC) at each grid point is derived from the volumetric water content (VWC), the wilting point (WP) and porosity (PO), which are characteristics of the present soil type, in the following way:

$$\text{RWC} = \frac{\text{VWC} - \text{WP}}{\text{PO} - \text{WP}} \quad (1)$$

We included the formula and some comments on the calculation in section 2.2. The field capacity was not reached by changing the soil moisture in our model runs.

Changes to paper:

“The relative water content is computed at each grid point from the volumetric water content (VWC) and the soil type dependent wilting point (WP) and porosity (PO) as follows:

$$w_{so} = \frac{VWC - WP}{PO - WP}. \quad (2)$$

”

3. The smoothing of the orography not only modifies the static stability of the atmosphere, but also the moisture content by including/excluding parts of the moisture-laden lower troposphere. CIN/CAPE is one measure to predict the amount of convection that will occur. Another measure is the amount of moisture stored in the atmosphere that can be tapped by the convection. I suggest to include a plot showing the integrated precipitable water before the onset of convection for the different sensitivity experiments. On page 11, lines 11-12 it is stated that the total precipitable water changes. I think it is important to show these plots and to interpret the results. Page 1, line 20: ”but that precipitation amount depends ...” in my opinion it is not only the strength of the trigger mechanism, but also the amount of moisture available for precipitation formation.

The remark in the text refers to modifications of the soil moisture which has a small impact on the precipitable water via evaporation. The largest changes (relative to the reference run) occur in the wet (SM_125) and dry (SM_075) experiments and range between -1.47% and +1.04%. As the reviewer correctly states, the smoothing of the terrain leads to a slight reduction of the terrain height. However, the response of precipitable water in those runs is an order of magnitude less than in the soil moisture experiments right before the convection is initiated (-0.61%+0.28%). Due to these small values, we decided not to include an extra figure, but rather add one sentence in section 3.2 describing the orography perturbations:

Changes to paper:

“We must further evaluate if the smoothing of terrain features, leading to somewhat lower terrain heights, has any implications on the precipitable water content. The analysis of the temporal evolution of precipitable water reveals that only marginal changes with respect to the reference run occur (relative deviations ranging between -0.61% and +0.28%), which indicates a negligible effect.”

4. Page 4, sensitivity studies: Please describe the generation of the random patterns in more detail.

For the generation of the random patterns we first use the python function `numpy.random` to create a random field consisting of 0 and 1. Subsequently, we convolve the pattern (using `scipy.convolve`). For this, we use two filters, which are derived from a Gaussian distribution, and which employ different expected values and variances. We then determine the length scale by looping through every 20th line in east-west direction and count the number of connected points with either positive or negative bias. We then average these values and find that the setting chosen for the small-scale random patterns has on average 20 connected points (10 km) with positive/negative bias and the larger-scale random patterns has on average 50 connected points.

We believe that such a detailed technical information does not need to be included in the paper, as the random patterns were generated just once and solely consist of dry and wet patterns at model initialization. Furthermore, the patterns are shown in Fig. 2. We slightly modified the text describing the random structures, it now reads:

Changes to paper:

“Similarly, dry and wet patches were distributed randomly using a Gaussian filter, leading to

small-scale (SM_RS) or larger-scale (SM_RM) patterns.”

5. Page 5, lines 5-7: ”we therefore conclude that ...” in my opinion this is not a valid statement as apples are compared with pears. The perturbation that is applied in the simulations with the altered soil-water content is much larger than just shifting around the soil water, but not changing its magnitude.

There is no such statement on page 5. We believe that the reviewer refers to page 7 and sentence in the conclusions. We agree with the reviewer that changing the soil moisture has a much larger effect than just redistributing the reference soil moisture in uniform dry and wet patches. But that is exactly what we wanted to investigate and believe that this statement is valid. We changed this sentence to:

Changes to paper:

“We therefore conclude that the initial soil moisture amount is much more important than the spatial distribution of dry and wet patches assuming a constant spatial average.”

6. Page 8, lines 23-24: ”since the structure scales ...” what does this imply for the S values in the other sensitivity tests?

For the CCN experiments, the structure component of the maritime runs are always lower than the remaining ones. This systematic behavior is not present for the other sensitivity. Because of that, we do not think that any implications for the other sensitivity tests need to be mentioned here.

Changes to paper: none

7. Paragraph 3.2: within this paragraph an attempt to validate the SAL metric is mixed with results on the different perturbation techniques. This makes it hard to read the paper. The manuscript would benefit if you split the text into an evaluation part and a results part.

When writing the first version of the paper, we also thought a lot about the structuring of the results. In the first part of section 3.2, only the 24-h averaged SAL-analysis is discussed. The analysis of the temporal evolution of the *A*-component is then mixed with other metrics to explain their differences. In our opinion, these points should not be separated. We already structured the text in the paragraphs Orography, Soil moisture, and Aerosols.

Changes to paper:

For a better distinction between the 24-h averaged analysis and the temporal evolution, we now moved the last point into a new section 2.3 called *“Factors determining the rain amount”*.

8. Page 9-10, section Orography: In the text the development of the grid-scale (resolved) convection is discussed. Yet, a parameterization scheme for shallow convection is active. When is sub-grid scale convection initiated in the different experiments, and how much of the instability is being eroded by the shallow convection parameterization scheme?

From the existing code and model output, it is not possible to depict time and location of parameterized shallow convection. However, the parameterization of shallow convection is only used at 2.8 km grid length which serves as IBC for our 500-m runs. In the latter, the scheme is switched off as shallow convection is explicitly resolved at that scale. So, all sensitivity runs were run with 500-m grid spacing without any convection parameterization.

Changes to paper:

We added these remarks in section 2.1:

2.8 km:

“Whereas deep convection is fully resolved, shallow convection is parameterized with a modified Tiedtke scheme with moisture-convergence closure (Tiedtke, 1989). Shallow convection is limited to a cloud depth of 250 hPa and is non-precipitating (see Baldauf et al. (2011) and Theunert and Seifert (2006) for details).”

500 m:

“Deep as well as shallow convection are now fully resolved and the Tiedtke schemes for shallow and deep convection are both switched off.”

9. How long are the simulations run for? Are there any spinup effects? Are the differences largest during the initial phase, or does the difference saturate, or even decrease, once the model has re-adjusted after the initial perturbation?

All simulations had an integration time of 24 h. We included that information in section 2.1.

In our COSMO simulations, spin-up effects are also present (e.g. increased wind-convergence or some weak and isolated precipitation). After 2–3 h of simulation time, no spin-up effects are apparent anymore, even for the strongest modifications (smoothing of the orography or large soil moisture gradients).

Changes to paper:

We also included that information in section 2.1.

Specific comments:

- Page 2, line 11: I suggest to replace ”uncertainties” by ”states” or ”conditions”, as no analysis of the underlying uncertainties is given.

We replaced uncertainties with conditions.

- Page 3, line 1: replace ”barrier” by ”barriers”, or include ”a” before ”stable”

Done, the text now reads: barriers.

- Page 3, lines 14-22: to my knowledge there are two papers addressing the combined effect of soil-moisture perturbations and orography: Rihani et al. (2015), and Imamovic et al (2017).

Thank you for pointing that out. Both of these papers use idealized simulations to isolate effects of terrain and soil moisture. We included them together with some new text:

Changes to paper:

“Up to now, there exist only studies with idealized simulations on the isolated and collective effects of terrain and soil moisture heterogeneity. Rihani et al. (2015) conducted large eddy simulations and found that terrain effects dominate the planetary boundary layer development during early morning hours, while the soil moisture signature overcomes that of terrain during the afternoon. With convection-resolving simulations, Imamovic et al. (2017) found a consistently positive soil moisture-precipitation feedback for horizontally uniform perturbations, irrespective of the presence of low orography. However, a negative feedback emerged with localized perturbations. In both of these studies, terrain modifications were much more extensive via flattening of the idealized mountains. Moreover, uncertainties of the aerosol load were not addressed.”

- Page 4, line 1: replace ”implies” by ”includes”

Done

- Page 4, line 13: replace ”coefficients are active” by ”diffusion is active”

Done

- Page 4, line 24: replace "physical" by "physically"

Done

- Page 7, line 12: replace "dependancy" by "dependency"

We changed dependance to dependence, there was no dependancy in this line.

- Page 7, line 13: include "a" before "heterogeneous"

Done

- SAL technique: I suggest to use bold, italic or calligraphic letters for A, L, or S in the text.

We now use italic letters throughout the entire manuscript, without marking it in the track-changed version.

- Page 8, line 10: replace "as" by "than"

Done

- Page 11, line 9: replace "as" by "than"

Done

- Page 11, Aerosols section: what about the collection processes of the falling cold hydrometeors, e.g. self-collection of graupel and hail, collection of rain by graupel or hail?

The collection of rain or cloud water by cold hydrometeors is included in the riming rate, this was already stated in the text: "...riming (collision of a droplet and an ice crystal)". The self-collection of graupel and hail is not included in the two-moment scheme of the COSMO model.

Changes to paper: none

- Page 12, line 19-21: "we therefore conclude that...more important...", more important for what? As stated earlier, I dont think that this is a very meaningful statement.

Please see our reply 5.:

Changes to paper:

"We therefore conclude that the initial soil moisture amount is more important than the spatial distribution of dry and wet patches assuming a constant spatial average."

- Page 12, line 29: either remove "to" before "precipitation", or replace "yield" by "lead"

The text now reads: "...can lead to precipitation deviations..."

- Page 12, line 32: replace "forecast" by "forecasting"

Done

- Figure 4: the symbols indicating the different sensitivity runs are very hard to read.

We increased the size of the symbols for better readability. Since even bigger symbols will overlap each other, we cannot increase the symbol size any further.

- Figure 6: I suggest to include the reference simulation at (0,0)

The reference simulation is obviously positioned at (0,0). An extra point at that place would make Fig. 4 (e) and (d) harder to read, as many other points lie close to zero there. We therefore decided not to include the reference simulation.

Rihani, J. F., F. K. Chow, and R. M. Maxwell. 2015. Isolating effects of terrain and soil moisture heterogeneity on the atmospheric boundary layer: Idealized simulations to diagnose land-atmosphere feedbacks. *Journal of Advances in Modeling Earth Systems* 7, 915-937.

Imamovic, A., L. Schlemmer, and C. Schär. 2017. Collective impacts of orography and soil moisture on the soil moisture-precipitation feedback. *Geophysical Research Letters*, 44, doi:10.1002/2017GL075657.

Reviewer 2

General comments:

The results from simulation with varying soil moisture, orography (including other external data) and CCN concentrations were compared to each other and conclusions that soil moisture and CCN concentration can affect precipitation significantly were drawn. However, it is not clear to me, how the variation in the initial model conditions compare to each other. Soil moisture differences compare to differences which can occur between observed and modeled soil moisture content. CCN concentrations are described as varying between maritime and polluted conditions. How does this compare to observations? Modification in the orography are based on smoothing to coarser model resolution. How strong do these changes vary eg. compared to variation which can be achieved by tuning the orographic smoothing? Instead of addressing the question on how the resulting precipitation differs, I would rather ask the question how much one variable (eg. aerosol) needs to be changed to achieve the same model spread in precipitation as by a change in soil moisture content by eg. 25%. In the end the fact that soil moisture affects precipitation strongest can also be a result of the strength by which the soil moisture was modified. Preferable to do this an independent ensemble spread would provide a first estimate or the comparison to observational data which are present from the previous study from Schneider. Also possible to use the coarse scale simulation as reference comparison. While a lot of effort was put in conducting a very comprehensive model study, the analysis is lacking and often confusing. For example, mean values of the SAL score are calculated which are later revised as the A value is not representative. Page 10 Line 13 to 22 describe why the previously used values of A are not representative

To our knowledge, this is the first time that the relative contribution of three specific sources of uncertainty involved in the initiation and formation of convective precipitation is investigated. Further, the distinction of different weather regimes comprises a novel element highlighting their larger impact during weak synoptically forced weather, an effect often being veiled when using bulk forecast statistics.

The three types of perturbations were specifically chosen as they are involved in the initiation and formation of convective precipitation at different stages of the process chain. We agree with the reviewer that it is difficult to compare our three sensitivities, as the relative strength of modification is hard to establish. But our perturbations are chosen based on realistic values. The soil moisture difference of 25% was selected because Hauck et al. (2011) showed that simulated and observed soil moisture in southwestern Germany differ around 20–30%. The soil moisture perturbation length scales were also used in earlier work (Baur et al. 2018). The CCN concentrations was varied between maritime and polluted conditions, all of which may exist in the domain under investigation. For the terrain forcing, we wanted to apply a method for the entire model domain for comparability to the other sensitivities, instead of more radical terrain modifications, e.g. the flattening of individual mountain ranges (see Schneider et al. 2018) which locally can have a strong effect. The terrain modification seems to be the one with the least effect. On average, those modifications have the smallest impacts on the 24-h precipitation amount. However, on half of the days analyzed here, they have a similar range of impact than different aerosol assumptions. Therefore, we believe that our conclusions are still valid for our specific modifications.

Usually, the SAL-analysis is conducted for longer time periods as e.g. the 24-h precipitation amount. As the timing of precipitation is then not taken into account, we decided to compute SAL-values based on hourly precipitation as e.g. in the study of Henneberg et al. (2018). The averaged SAL diagram then gives a more reliable information as the SAL-values computed only from the 24-h precipitation amount. As positive and negative values can cancel themselves out during the period considered, we decided to also show the temporal evolution of the A-component. We believe that this is not a

weakness of our method, but rather a benefit of having both information.

Specific comments:

- Abstract: Page 1 Line 13: correct initial values are much more important than the spatial distribution... What is meant by correct initial values? I think what is meant is something like: The amount of soil moisture affects precipitation stronger than its spatial distribution.

Yes, that's what we meant. We adapted the text accordingly.

Changes to paper:

"We therefore conclude that the initial soil moisture amount is much more important than the spatial distribution of dry and wet patches assuming a constant spatial average."

- Page 1 Line 18: ...that the structure component is highest in the soil moisture... Are structure values really higher for all soil moisture and CCN simulations or is structure most sensitive to changes in soil moisture (content) and CCN concentration. Also, I would avoid talking about structure in the abstract as the concept of SAL is not clear to the reader yet. What does structure mean? – Intensity of precipitation?

On average, the highest S values occur for the aerosol and soil moisture modifications. The mean values were presented in section 3.2. We added "on average" and a short explanation for the structure component in the abstract which, to our opinion, should be sufficient information for the reader:

Changes to paper:

"These diagnostics reveal that the structure component, comparing the size and shape of precipitating objects to the reference simulation, is on average highest..."

- Page 1 Line 19: ...dominant mechanism for convection initiation... trigger mechanism What are these mechanisms?

The trigger mechanism are e.g. low-level wind convergence with subsequent lifting of air parcels. This is analyzed in section 3.2. We do not think that a further explanation in the abstract is needed for that.

Changes to paper: none

- Page 1 Line 20: Location and amplitude parameters are both much smaller. Change to: Location and amplitude parameters both vary over a much smaller range.

Done

- Introduction: Missing explanation about the soil moisture precipitation feedback.

There is an entire paragraph related to the soil moisture–precipitation feedback in the Introduction (P2, L23–P3, L4). We believe that it is sufficiently addressed.

Changes to paper: none

Missing: The conclusion of the study is to include soil moisture and aerosol variation in ensemble forecast to achieve a sufficient model spread? An overview of how ensemble spreads are generated in current ensemble setups would be beneficial.

This is a good point, we included this text in the Introduction:

Changes to paper:

"Ensemble forecasting has become a standard tool for probabilistic numerical weather prediction and most major meteorological services now run such systems routinely (e.g., Bouttier et al.

(2018)). *Key uncertainties that are accounted for comprise, e.g., the uncertainties in the initial and lateral boundary conditions as well as uncertainties in the representation of physical processes (e.g., Clark et al. (2016), and references therein.)*”

- Page 2 Line 26: What is meant by soil moisture assumptions? Assumptions in the formulation in the couple soil model or assumptions about the soil moisture content?

We mean assumptions about the soil moisture content and adapted the text accordingly.

- Page 3 Line 17: Aerosol or CCN? I think the study is constrained to changes in the CCN concentration while the freezing /nucleation scheme remains untouched?

Aerosols serve as cloud condensation nuclei (CCN) and ice nuclei (IN), therefore we use both terms “*aerosol*” or “*CCN concentration*” in the text. In the model, we just change the CCN concentration and not the IN concentration. We included that information in section 2.1 describing the model set-up:

Changes to paper:

“Heterogeneous ice nucleation on aerosol particles serving as ice nuclei (IN) is parameterized following Phillips et al. (2008) with the IN concentration left constant throughout the simulations.”

- Methods: Why chess board like structure to modify soil moisture field. That looks like a very artificial change and could cause artificial circulation. Is the domain average soil moisture content the same? How are the random perturbations generated?

We agree with the reviewer that a chess board structure is a very artificial and idealized change. However, we believe that the uncertainty in soil moisture can be represented by such structures, as e.g. after scattered showers or after postfrontal convection, roughly similar wet and dry patches can be created. Chess board structures were also used by Courault et al. (2007) or Baur et al. (2018). Further studies with chessboard-type inhomogeneities of the surface are e.g.:

Tsvang, L.R., M.M. Fedorov, B.A. Kader, S.L. Zubkovskii, T. Foken, S.H. Richter, J. Zeleny, 1991: Turbulent exchange over a surface with chessboard-type inhomogeneities. *Bound.-Layer Meteor.* 55, 141160.

Friedrichs, K, Mölders, N, Tetzlaff, G (2000): On the influence of surface heterogeneity on the Bowen-ratio: A theoretical case study. *Theor Appl Climatol* 65: 181-196.

Rieck, M., C. Hohenegger, and C.C. van Heerwaarden, 2014: The Influence of Land Surface Heterogeneities on Cloud Size Development. *Mon. Wea. Rev.*, 142, 38303846, <https://doi.org/10.1175/MWR-D-13-00354.1>

Lee, J.M., Y. Zhang, and S.A. Klein, 2019: The Effect of Land Surface Heterogeneity and Background Wind on Shallow Cumulus Clouds and the Transition to Deeper Convection. *J. Atmos. Sci.*, 76, 401419, <https://doi.org/10.1175/JAS-D-18-0196.1>

The generation of secondary circulations along soil moisture gradients has been documented in many studies and is an intended feature of our simulations. As we are aware that the chessboard structure is highly idealized, we additionally introduced randomly distributed dry and wet patches.

For the generation of the random patterns we first use the python function `numpy.random` to create a random field consisting of 0 and 1. Subsequently, we convolve the pattern (using `scipy.convolve`). For this, we use two filters, which are derived from a Gaussian distribution, and which employ different expected values and variances. We then determine the length scale by

looping through every 20th line in east-west direction and count the number of connected points with either positive or negative bias. We then average these values and find that the setting chosen for the small-scale random patterns has on average 20 connected points (10 km) with positive/negative bias and the larger-scale random patterns has on average 50 connected points.

We believe that such a detailed technical information does not need to be included in the paper, as the random patterns were generated just once and solely consist of dry and wet patterns at model initialization. Furthermore, the patterns are shown in Fig. 2. We slightly modified the text describing the random structures, it now reads:

Changes to paper:

“Similarly, dry and wet patches were distributed randomly using a Gaussian filter, leading to small-scale (SM_RS) or larger-scale (SM_RM) patterns.”

- How exactly are the inhomogeneous CCN concentration generated? Even though, CCN concentration can vary spatially I would assume they are advected similar to the clouds (at least in strong forcing cases). Clouds which travel through region with strongly varying aerosol conditions seem to be rather unrealistic to me and I fear this causes unphysical affects? In weak forcing cases I would assume the effect of this CCN perturbation is randomly depending on where convection is triggered with respect to the CCN modification.

Our model has 4 prescribed CCN concentrations and therefore we decided to use these values. We created squares with 112 x 112 grid points (56 x 56 km to resemble the soil moisture chess boards) that have the same CCN concentration and then placed 6x4 of these squares together (by hand) such that the mean concentration is close to 1700 cm-3 (as in the reference simulation), and that no squares with the same concentration are located next to each other, except that we allow for diagonal connections. These large patterns were then repeated throughout the domain (Fig. R.2). Note that CCN themselves are not transported in our simulations.




Figure R.2: Spatially heterogeneous CCN concentrations in the VAR experiment.

We believe that it is not unrealistic that clouds travel through regions with varying CCN concentrations, as e.g. larger cities or industrial regions can lead to local polluted conditions. Moreover, our patch size is comparatively large, so that convective clouds do not travel over many different patches (in particular for weak synoptic forcing). No artificial errors are introduced when using

the horizontally-varying CCN. In idealized tests, cells moving across a CCN boundary adapted slowly to their new CCN environment only through changes to the number of cloud drops activated (consistent with the new CCN environment). This means convective cells moving into regions of higher CCN concentration change relatively quickly (5-10 mins; as a larger number of cloud drops are activated near cloud base and are transported through the cloud), whereas cells moving into regions of lower CCN concentrations take longer to adjust (20-30 mins; because fewer cloud drops are activated near cloud base, but the large number of cloud drops existing throughout the cloud persist). This is exactly consistent with how a real convective cell would react to changes in the CCN environment.

For the weakly forced cases, we agree with the reviewer that aerosol–cloud interactions will depend on where convection is initiated. However, convection is widely distributed in our model domain (see Fig. 3 in manuscript), so that the clouds form in all four different CCN concentration patches (Fig. R.2).

Changes to paper: none

- I assume the changes in the smoothing of external data affecting the orography is only relevant in regions with complex topography, while the modifications in soil moisture and CCN concentrations are applied across the whole model domain.

Yes, that is correct, the smoothing of the terrain primarily influences complex terrain. However, the central and in particular the southern parts of Germany are characterized by low mountain ranges which are affected by our modification technique.

Changes to paper: none

- Page 4 Line 24: Change to homogenous soil moisture is done for all model levels. From that it is not clear if all soil moisture perturbations are applied on all soil layers.

Yes, all soil model levels have been modified in the same way. We deleted the first remark and included this sentence at the end:

Changes to paper:

“To assure physical meaningful soil moisture profiles, all soil moisture modifications mentioned above are done for all soil model levels.”

- Table 1: Maybe I missed it: what is the aerosol concentration in the reference run? In the text it says simulations with modified terrain and soil moisture run with 1700 cm^{-3} . Is this also the case for the reference run? If so, I wonder what the difference to CON is.

The reference simulation uses the continental aerosol assumption of 1700 cm^{-3} .

Changes to paper:

We inserted a sentence in section 2.1 to make that clear. There is no difference to CON, we therefore included some text in the heading of Table 1 and included CON(=REF) in the aerosol block of the table.

- The simulations were compared to radar observations in a previous study. The present study would highly benefit from including this comparison eg. also by using SAL analysis. This provides a reference deviation for a better quantification of the variations in precipitation that occur from different model settings.

In the previous study of Schneider et al. (2018), only a qualitative comparison of Radar-derived with the simulated precipitation amount of the reference runs was made. As in this study, we believe that a qualitative good representation of the weather characteristics is sufficient and a quantitative analysis not necessary, as the focus lies on the sensitivity of the model to orography,

soil moisture, and CCN concentrations. Moreover, the radar-derived precipitation has a coarser resolution which would require an interpolation with loss of small-scale details. We therefore did not include any new figures or text.

Changes to paper: none

- Results: For the analysis SAL was used. While the A value mainly describes the changes in precipitation amount, it does not give much more information as the comparison of the precipitation amount. However, the S value gives information of whether precipitation becomes more intense and locally constrained (deeper convection) or increases in size. For that it is important to have A as comparison in order to derive if a change in structure is caused by a change in the area or intensity. This connection was not drawn in the analysis. Further, the averaging over SAL values over time diminish some effects. I'm not sure what the worth of an averaged SAL values are. Especially later the relevance and correctness of the A-value is often questioned.

Usually, the SAL-analysis is conducted for longer time periods, e.g. the 24-h precipitation amount. As the timing of precipitation is then not taken into account, we decided to compute SAL-values based on hourly precipitation as e.g. in the study of Henneberg et al. (2018). The averaged SAL diagram then gives a more reliable information as the SAL-values computed only from the 24-h precipitation amount. As positive and negative values can cancel themselves out during the period considered, we decided to also show the temporal evolution of the A-component. We believe that this is not a weakness of our method, but rather a benefit of having both information.

The connection between S and the rain intensity/amount was already described at in the section about the averaged SAL-values. We believe that a more detailed information (e.g. the correlation of S and A) is not absolutely mandatory for the reader to understand our main points.

Changes to paper: none

- Page 6 Line 17: ...the sensitivity to terrain forcing always shows the smallest spread. As already mentioned above, I find this hard to judge as the sensitivity highly depends on the strength on variation.

We agree with the reviewer that the terrain modification seems to be the one with the least effect. On average, those modifications have the smallest impacts on the 24-h precipitation amount. However, on half of the days analyzed here, they have a similar range of impact than different aerosol assumptions. There are more radical terrain modifications possible, e.g. the flattening of individual mountain ranges (see Schneider et al. 2018) which locally can have a strong effect. However, we decided to use the smoothing of terrain features as this is a modification done in the entire model domain and thus better comparable to soil moisture and CCN modifications.

Changes to paper: none

- Page 6 Line 25: How does stratiform precipitation match the title?

The cases under strong synoptic forcing do have stratiform and convective (embedded) precipitation. As the convective parts dominate the rain totals, we believe that our title is still correct.

Changes to paper: none

- Page 8 Line 2-3: Change small to negative Change too small to smaller. Too smaller sound as if this is wrong but it is just different to the reference case. Change large to positive.

Thanks for pointing that out, it is corrected.

- Page 8 Line 11: Are the SAL values smaller compared to other studies because of the model to model comparison or because of the averaging?

In general, they are smaller because we compare the sensitivity runs to the reference run and not an observation. However, the averaging can also lead to smaller values as positive and negative values can cancel themselves out.

Changes to paper: none

- Page 8 Line 29: On weak forcing days, there are simulations, in which the amplitude does not reflect the precipitation sum? So, what is the sense of the previous analysis than. This makes it really difficult to follow. Also on Page 10 Line 21.

In this line, the days with strong synoptic forcing is discussed. In that section, we present the results from the averaged SAL-analysis which can be influenced by positive and negative values which can cancel themselves out and lead to a small A component. This is exactly why we added the temporal analysis of the A-component to better explain the precipitation totals.

Changes to paper: none

- Page 10 Line 7: Change especially to only.

Done

- Page 10 Line 24: Bowen ration not introduced yet. What does Bowen ration above 1 mean? Higher latent or sensible heat?

Thanks for pointing that out. We included an explanation, the text now reads:

Changes to paper:

“During daytime, the Bowen ratio β (i.e. the ratio between the sensible and latent heat flux) increases to values larger than 1 in the SM_075 simulation as a result of the dominating sensible heat flux.”

- Page 10 Line 28: What is the relation between CAPE and A-component? Why does precipitation increase with reduced CAPE? (If my interpretation of positive A is correct). In Line 30 the argument is, that enhanced CAPE enhances precipitation. In this argumentation I miss arguments about the changed moistening of the atmosphere, what is needed to trigger, convection, destabilize the atmosphere and also to provide enough moisture for precipitation. Showing some more results about convective parameters such as surface temperature, CAPE or LCL developments may support the argumentation.

Thanks for pointing that out, our first text version was misleading. We rewrote that part:

Changes to paper:

“As a result of the weaker latent heat flux, the lifting condensation level is higher (not shown) and CAPE is reduced compared to the SM_125 simulation. Despite that reduction in CAPE, the model still simulates higher rain intensities in the SM_075 simulation than in the reference run. This can be explained by the stronger lifting from low-level wind convergence and the fact that there is still enough CAPE in the atmosphere to allow for deep convection to develop. This leads to higher rain intensities between 10:00–14:00 UTC compared to the reference or SM_125 simulation which are also represented by a positive A (Fig. 8i).”

For the sake of brevity, we decided not to show additional variables (T2m or LCL) as suggested, because we believe that the text alone is sufficient.

- Page 12 Line 1: What kind of precipitation is found below cloud base (rain or snow). Is it only a size argument what makes them less susceptible to evaporation (or sublimation)?

Below cloud base, the model simulates rain only (at least when averaged over the model domain) and no snow or graupel. The effect of evaporation is based on a size argument, but it was also evident from process rates and derived particle size distributions.

Changes to paper: none

- Page 12 Line 20: What are correct initial values?

We rephrased that sentence as also reviewer 1 had concerns:

Changes to paper:

“We therefore conclude that the initial soil moisture amount is more important than the spatial distribution of dry and wet patches assuming a constant spatial average.”

- Technical comments: Page 2 Line 10: the state of the atmospheric Atmosphere or atmospheric condition

It should be *“state of the atmosphere”*, it is corrected.

- Page 11 Line 27: switch 28 July and 11 September as in the text above 28 July is also mentioned first

Done

Relative impact of aerosol, soil moisture and orography perturbations on deep convection

Linda Schneider, Christian Barthlott, Corinna Hoose, and [Andrew I. Barrett](#)

Institute of Meteorology and Climate Research (IMK-TRO), Karlsruhe Institute of Technology (KIT), Germany

Correspondence: Christian Barthlott (christian.barthlott@kit.edu)

Abstract. The predictability of deep moist convection depends on many factors such as the synoptic-scale flow, the geographical region (i.e., the presence of mountains), land surface–atmosphere as well as aerosol–cloud interactions. This study addresses all these factors by investigating the relative impact of orography, soil moisture and aerosols on precipitation over Germany in different weather regimes. To this end, we conduct numerical sensitivity studies with the COnsortium for Small-sale MOdelling (COSMO) model at high spatial resolution (500 m grid spacing) for six days with weak and strong synoptic forcing. The numerical experiments consist of (i) successive smoothing of topographical features, (ii) systematic changes in the initial soil moisture fields (spatially homogeneous increase/decrease, horizontal uniform soil moisture, different realizations of dry/wet patches), and (iii) different assumptions on the ambient aerosol concentration (spatially homogeneous and heterogeneous fields). Our results show that the impact of these perturbations on precipitation is on average higher for weak than for strong synoptic forcing. Soil moisture and aerosols are each responsible for the maximum precipitation response for three of the cases, while the sensitivity to terrain forcing always shows the smallest spread. For the majority of the analyzed cases, the model produces a positive soil moisture–precipitation feedback when averaged over the entire model domain. ~~Furthermore, correct initial values are much more important than the spatial distribution of dry and wet patches~~ Furthermore, the amount of soil moisture affects precipitation stronger than its spatial distribution. The precipitation response to changes in the CCN concentration is more complex and case dependent. The smoothing of terrain shows weaker impacts on days with strong synoptic forcing because surface fluxes are less important and orographic ascent is still simulated reasonably well, despite missing fine-scale orographical features. We apply an object-based characterization to identify if and how the perturbations affect the structure, location, timing, and intensity of precipitation. These diagnostics reveal that the structure component ~~is~~, comparing the size and shape of precipitating objects to the reference simulation, is on average highest in the soil moisture and aerosol simulations, often due to changes in the maximum precipitation amounts. This indicates that the dominant mechanisms for convection initiation remain, but that precipitation amounts depend on the strength of the trigger mechanisms. Location and amplitude parameters ~~are both much smaller~~ both vary over a much smaller range. Still, the temporal evolution of the amplitude component correlates well with the rain rate. Our results suggest that for quantitative precipitation forecasting, both aerosols and soil moisture are of similar importance and that their inclusion in convective-scale ensemble forecasting containing classical sources of uncertainty should be assessed in the future.

1 Introduction

Forecasting convective precipitation remains one of the key challenges in numerical weather prediction (NWP) and has large social, economic and environmental impacts due to the multiple risks from hail, lightning, strong winds, and heavy precipitation. Convective precipitation results from a chain of complex processes and multi-scale interactions in the atmosphere and is therefore accompanied by numerous uncertainties in its formation. Although convection-permitting models have provided a step-change in rainfall forecasting capabilities (Clark et al., 2016), current state-of-the art models still exhibit persistent and systematic shortcomings due to an inadequate representation of unresolved processes (Berner et al., 2017). This makes it difficult to properly predict convective precipitation, resulting in an often inadequate accuracy for many applications (Kühnlein et al., 2014; Mittermaier, 2014). The predictability of convective precipitation, i.e., the degree to which a correct prediction of the state of the ~~atmospheric~~ atmosphere can be made, depends on many aspects such as, among others, the synoptic-scale flow, the geographical region (i.e., the presence of mountains), the underlying land surface and microphysical ~~uncertainties~~ conditions. For thermally forced convection, physical understanding is further challenged by the essential nonlinearity of thermally driven circulations, large spatial heterogeneity in thermodynamics and winds over complex terrain, and multi-scale interactions between the land surface and the planetary boundary layer (e.g., Kirshbaum et al., 2018; Groenemeijer et al., 2009). Land surface properties (e.g., land cover, terrain, and soil texture) are highly heterogeneous across a wide range of spatiotemporal scales (Santanello et al., 2018) and potential linkages between land surface variables and atmospheric variables such as temperature and precipitation are difficult to establish (e.g., Seneviratne et al., 2010). Over mountainous terrain, thermally induced wind systems and low-level convergence zones are crucial for the initiation of deep convection with prevailing weak winds (e.g., Schneider et al., 2018). They are often less well resolved in operational models, which limits the forecast capabilities in contrast to situations governed by large-scale synoptic forcing, when the forecast of precipitation is often more reliable (Baldauf et al., 2011). Previous studies have shown that the knowledge of the orographically modified flow is essential to predict intensity, location, and duration of precipitation (e.g., Rotunno and Ferretti, 2001; Rotunno and Houze, 2007; Barthlott et al., 2016).

The relevance of soil moisture for convective precipitation has been investigated in many studies (e.g., Schär et al., 1999; Findell and Eltahir, 2003; Seneviratne et al., 2010; Richard et al., 2011). Despite a robust understanding that higher soil moisture leads to an increase in the near-surface specific humidity and a decrease in temperature, the soil moisture–precipitation feedback is highly complex and may vary spatially and temporarily (Pan et al., 1996). Furthermore, soil moisture ~~assumptions~~ contents in models often show large differences to observations (Hauck et al., 2011). The initial soil moisture content can be of large importance as well: For a case study, Barthlott and Kalthoff (2011) showed that for drier soils (where evaporation is controlled by soil moisture), a systematic positive soil moisture-precipitation feedback exists, whereas for already quite wet soils (where evapotranspiration is controlled by net radiation), the influence of increasing soil moisture is much weaker and the general response of precipitation to soil moisture is not systematic anymore. Additionally, the presence of horizontal land-surface wetness gradients, which induce gradients in the sensible heat flux, can foster mesoscale circulations, resulting

in more precipitation over dry soils (Taylor et al., 2012). A negative soil moisture–precipitation feedback was also found for convection-resolving simulations by Hohenegger et al. (2009). In their simulations, dry initial soil moisture conditions yield more vigorous thermals (owing to stronger daytime heating), which can more easily break through stable air ~~barrier~~-barriers above, thereby leading to deep convection and ultimately to a negative soil moisture–precipitation feedback loop. Moreover, the strength of the background wind was found to change precipitation patterns even more (Froidevaux et al., 2014; Guillod et al., 2014), leading to a non-systematic soil moisture–precipitation feedback.

Besides the unclear roles of the underlying terrain and the soil moisture–precipitation feedback in different weather regimes, there are large uncertainties arising from the nonlinear character of the microphysics and the complexity of the microphysical system with many possible process pathways (Seifert et al., 2012). Many recent studies documented that the response of clouds to changes in the aerosol concentration is complex and may differ depending on the cloud type or aerosol regime or environmental conditions (e.g., Khain et al., 2008; Noppel et al., 2010; van den Heever et al., 2011; Barthlott and Hoose, 2018), and may be complicated by processes below clouds, such as evaporation (e.g., Barthlott et al., 2017). Moreover, the validity of the invigoration hypothesis (Rosenfeld et al., 2008) in polluted conditions (i.e., updraft invigoration by additional latent heating due to a larger water load above the freezing level) and the possibility of climate responses to this effect are still considered to be open questions (Altaratz et al., 2014).

Ensemble forecasting has become a standard tool for probabilistic numerical weather prediction and most major meteorological services now run such systems routinely (e.g., Bouttier and Raynaud, 2018). Key uncertainties that are accounted for comprise, e.g., the uncertainties in the initial and lateral boundary conditions as well as uncertainties in the representation of physical processes (e.g., Clark et al., 2016, and references therein). To address predictability thoroughly, relevant sources of uncertainty need to be identified. While terrain forcing, soil moisture, and aerosol impacts on convective precipitation have been investigated separately in many studies, the relative effect of these perturbations for the same weather situations has not been investigated so far. Up to now, there exist only studies with idealized simulations on the isolated and collective effects of terrain and soil moisture heterogeneity. Rihani et al. (2015) conducted large eddy simulations and found that terrain effects dominate the planetary boundary layer development during early morning hours, while the soil moisture signature overcomes that of terrain during the afternoon. With convection-resolving simulations, Imamovic et al. (2017) found a consistently positive soil moisture-precipitation feedback for horizontally uniform perturbations, irrespective of the presence of low orography. However, a negative feedback emerged with localized perturbations. In both of these studies, terrain modifications were much more extensive via flattening of the idealized mountains. Moreover, uncertainties of the aerosol load were not addressed. Thus, the aim of this study is to investigate the uncertainties that variations in orography, soil moisture and aerosols impose on convective precipitation by means of real-case simulations. To cover different weather regimes typical for central Europe, we analyze days with weak large-scale forcing (airmass convection) and strong large-scale forcing (passage of frontal zones). This study is unique as it is the first (to the best of our knowledge) to address the relative impacts of these uncertainties on convective-scale predictability. It is of general relevance to assess to which extent these uncertainties should be considered in future convective-scale ensemble forecasting systems.

2 Methods

2.1 Numerical model

The general model setup follows the one from Schneider et al. (2018). All simulations were conducted with version 5.3 of the COnsortium for Small-sale MOdelling (COSMO) model (Schättler et al., 2016). It is a non-hydrostatic limited-area atmospheric prediction model, which operates on a rotated latitude/longitude grid with an Arakawa C-grid for horizontal differencing. First, simulations are performed with 2.8-km grid spacing on the operational COSMO-DE grid of the German Weather Service driven by 7 km COSMO-EU initial and boundary data (see Schneider et al. (2018) for exact domain location). The model uses terrain-following coordinates and 50 levels in the vertical. The time integration is realized using a two-time level Runge-Kutta method (Wicker and Skamarock, 2002), the time step is set to 25 s. Whereas deep convection is fully resolved, shallow convection is parameterized with a modified Tiedtke scheme (Tiedtke, 1989) with moisture-convergence closure (Tiedtke, 1989). Shallow convection is limited to a cloud depth of 250 hPa and is non-precipitating (see Baldauf et al. (2011) and Theunert and Seifert (2006) for details). We use a 1-D turbulence scheme, which is based on a prognostic equation for the turbulent kinetic energy and can be classified as Mellor-Yamada level 2.5 (Mellor and Yamada, 1974). The model further implies-includes a multilayer soil vegetation model TERRA-ML (Doms et al., 2011) with six soil levels. In contrast to the operationally used setup, we use the two-moment microphysics scheme of Seifert and Beheng (2006) for representing aerosol effects on the microphysics of mixed-phase clouds. The two-moment scheme predicts mass and number concentration of six different hydrometeors (cloud water, rain, cloud ice, graupel, snow and hail) and allows to use different constant cloud condensation nuclei (CCN) concentration assumptions. The preprocessing of the initial and boundary data is done with the preprocessor INT2LM (Schättler, 2016).

Then, a 500 m grid is nested into the 2.8 km domain using one-way interfaces (Fig. 1a). Such a fine grid resolution was also used in COSMO simulations exploring the gray zone by Barthlott and Hoose (2015). They showed several benefits compared to coarser resolutions, such as a better representation of low-level convergence zones or gravity waves. The domain size is reduced covering approximately 750×700 km (1510×1300 grid points) and spans almost entire Germany. The number of vertical levels is increased to 80, with 18 levels in the lowest kilometer. Deep as well as shallow convection are now fully resolved and the Tiedtke schemes for shallow and deep convection are both switched off. Instead of a 1-D boundary-layer approximation, turbulence is now parameterized with a 3-D closure, where both vertical and horizontal turbulent coefficients are-diffusion is active (Doms et al., 2011). The time step is reduced to 3 s for numerical stability. For this reference run, we use a continental aerosol assumption with a number density of 1700 cm^{-3} typical for central Europe (Hande et al., 2016). All simulations had an integration time of 24 h. Spin-up effects (e.g. increased wind convergence or weak isolated rain) are only simulated during the first 2–3 h of integration time, which do not affect the subsequent precipitation discussed herein.

2.2 Sensitivity studies

To address the relative impacts of land surface and aerosol heterogeneities on deep convection, we perform several numerical sensitivity studies which are summarized in Table 1. The successive smoothing of individual terrain features is realized by

Table 1. Overview of the performed numerical sensitivity simulations. The [reference run and all orography/soil moisture perturbations](#) use a [continental CCN assumption \(CON\)](#). The relative soil moisture content w_{so} is modified only at model initialization.

Name	Description	
REF	original orography ($\Delta x = 500$ m)	
EXT1000	smoothed orography from 1 km resolution	
EXT2800	smoothed orography from 2.8 km resolution	
EXT7000	smoothed orography from 7 km resolution	
SM_075	reduction soil moisture by 25 %	$w_{so} = 75\% w_{so,ref}$
SM_125	increase soil moisture by 25 %	$w_{so} = 125\% w_{so,ref}$
SM_10k	chess board structure with 10×10 km ² patch size	$w_{so} = \pm 25\% \bar{w}_{so}$
SM_56k	chess board structure with 56×56 km ² patch size	$w_{so} = \pm 25\% \bar{w}_{so}$
SM_112k	chess board structure with 112×112 km ² patch size	$w_{so} = \pm 25\% \bar{w}_{so}$
SM_UNI	homogeneous soil moisture field	$w_{so} = \bar{w}_{so}$
SM_RS	small-sized random structures	$w_{so} = \pm 25\% \bar{w}_{so}$
SM_RM	medium-sized random structures	$w_{so} = \pm 25\% \bar{w}_{so}$
MAR	maritime aerosol conditions	CCN = 100 cm^{-3}
INT	intermediate aerosol conditions	CCN = 500 cm^{-3}
CON (=REF)	continental aerosol conditions	CCN = 1700 cm^{-3}
POL	polluted aerosol conditions	CCN = 3200 cm^{-3}
VAR	chess board structure with MAR, INT, CON, POL patches of 56×56 km ²	CCN = 1678 cm^{-3}

taking external parameters (terrain height, land-use, roughness length etc.) at coarser resolution (1, 2.8, and 7 km), which are then interpolated onto the 500 m model grid (hereafter referred to as EXT1000, EXT2800, EXT7000). This results in somewhat lower mountain top heights and less well resolved valleys (Fig. 1). Such a technique was also applied by Schumacher et al. (2015) for studying banded convection in the lee of the Rocky Mountains and Picard and Mass (2017) for investigating the impact of the flow direction on orographic precipitation over the US Pacific Northwest.

The majority of the sensitivity runs in this study consists of different soil moisture assumptions (Fig. 2). First, a simulation with spatially homogeneous soil moisture is performed (SM_UNI), assuming for every grid point the domain-averaged relative water content \bar{w}_{so} . ~~This is done for all soil model levels to assure physical meaningful soil moisture profiles.~~ The relative water content is computed at each grid point from the volumetric water content (VWC) and the soil type dependent wilting point (WP) and porosity (PO) as follows:

$$w_{so} = \frac{\text{VWC} - \text{WP}}{\text{PO} - \text{WP}}. \quad (1)$$

Thus, there are no horizontal soil moisture gradients. Then, we introduce a positive and negative soil moisture bias by increasing (SM_125) or decreasing (SM_075) the initial soil moisture field by 25 % at every grid point. The value of 25 % was selected

Table 2. Investigated cases.

Day	Synoptic forcing	Characteristics
30 June 2009	weak	high pressure system over central Europe, weak mid-tropospheric winds
1 July 2009	weak	ridge over France, weak mid-tropospheric winds
23 July 2013	weak	ridge over Germany, weak mid-tropospheric winds
11 September 2011	strong	long-wave trough and low-pressure system west of the British Isles, strong mid-tropospheric winds
28 July 2013	strong	low-pressure system east of the British Isles, strong mid-tropospheric winds
11 September 2013	strong	low-pressure system over Germany, strong mid-tropospheric winds

because Hauck et al. (2011) showed that simulated and observed soil moisture in southwestern Germany differ around 20–30 %. Chess board structures are implemented with grid-lengths of 10 km (SM_10k), 56 km (SM_56k) and 112 km (SM_112k), in which moist and dry patches are regularly placed within the model domain. They represent conditions with $\pm 25\%$ of the domain-averaged soil moisture content. This technique was also applied by Baur et al. (2018) and in a similar way in large-eddy simulations by Courault et al. (2007). ~~Similarly, random structures with a~~ Similarly, dry and wet patches were distributed randomly using a Gaussian filter, leading to small-scale (SM_RS) or ~~with a~~ larger-scale (SM_RM) ~~pattern are implemented. On average, the~~ patterns. The small-scale random pattern has a patch length similar to the 10 km chess board structure. To assure physical meaningful soil moisture profiles, all soil moisture modifications mentioned above are done for all soil model levels. All simulations with modified terrain and soil moisture use continental aerosol assumptions (CON) with a number density of 1700 cm^{-3} .

To address microphysical uncertainties, we introduce three other homogeneous CCN concentrations: 100 cm^{-3} (maritime conditions, MAR), 500 cm^{-3} (intermediate conditions, INT) and 3200 cm^{-3} (polluted conditions, POL). Because aerosol concentrations are highly variable within the atmosphere (e.g., Hande et al., 2016), we also mimic a situation with spatially varying CCN concentrations and include a chess board structure as for the soil moisture. The tiles have grid-lengths of 56 km and the CCN concentrations of the tiles were attributed randomly, assuring that the domain-averaged ~~CCN~~ concentration is similar (1678 cm^{-3}) as in the reference simulation (1700 cm^{-3} , CON). The vertical CCN profile has a constant number density up to a height of 2 km and decreases exponentially above. Heterogeneous ice nucleation on aerosol particles serving as ice nuclei (IN) is parameterized following Phillips et al. (2008) with the IN concentration left constant throughout the simulations.

2.3 Cases analyzed

To investigate different weather regimes, we perform numerical simulations for three cases with weak synoptic forcing and for three cases with strong synoptic forcing. These are the same days already investigated by Schneider et al. (2018) who provided a detailed synoptic analysis and comparison of radar-derived and simulated precipitation totals. They showed that the model

captures the overall precipitation distribution reasonably well. Thus, we only list the days and main weather characteristics in Table 2 and refer to their study for more details.

The 24 h accumulated precipitation of all reference runs (500 m original orography, unchanged initial soil moisture, continental aerosol-CCN assumption) is shown in Fig. 3. During weak synoptic forcing, the model simulates isolated convective cells with a life time of around 1–3 h (Fig. 3a-c). A more stratiform precipitation distribution is simulated for strong synoptic forcing. For these days, also embedded convection (Fig. 3d,e) and orographic precipitation enhancement (Fig. 3f, southwestern Germany) is simulated.

3 Results

3.1 Precipitation amounts and timing

The precipitation response to land surface and aerosol heterogeneities is summarized using domain-averaged precipitation totals and their deviations from the respective reference run (Fig. 4). It can be seen that the average precipitation is much smaller on weak forcing days (1.6–2.8 mm) than on strong forcing days (6.0–8.1 mm). The impact of our perturbations on precipitation deviations, however, is on average higher for weak than for strong synoptic forcing. Soil moisture and aerosols are each responsible for the maximum precipitation response for three of the cases, while the sensitivity to terrain forcing always shows the smallest spread. In general, perturbations of the orography have a larger impact during weak forcing conditions, whereas for strong synoptic forcing, the impact is rather small. This could be explained by the fact that for orographic, more stratiform precipitation, the resolution of the external data is not that important, as mesoscale rising of air on mountains can still be reasonably well simulated without detailed valley structures. Interestingly, the simulations with smoothed terrain show a systematic positive offset compared to the reference run on four out of six days. Reasons for this could be the change in near-surface temperatures, which then modify the atmospheric stability. This will be discussed in more detail in the next section.

With precipitation deviations from the respective reference run between -12% on 23 July 2013 and up to $+15\%$ on 1 July 2009, the soil moisture simulations show the highest daily variability for weak forcing cases ~~-(Fig. 4b)~~. Furthermore, for all analyzed cases, the runs with reduced soil moisture (SM_075) always have the lowest precipitation amounts in this group of sensitivity. Positive precipitation deviations from the reference run are simulated with increased soil moisture (SM_125) indicating a positive soil moisture–precipitation feedback (except strong forcing case 28 July 2013). The impact of soil moisture on precipitation totals is generally smaller for strong than for weak synoptic forcing, which implies that land surface–atmosphere interactions are less important for weather regimes with approaching troughs or frontal systems. Different patches of dry and wet soils have, on average, smaller effects on the simulated precipitation amounts than the dry or wet bias experiments. We therefore conclude that ~~correct initial values are the~~ initial soil moisture amount is much more important than the spatial distribution of dry and wet patches assuming a constant spatial average.

The response of total precipitation to changes in the CCN concentration is more complex: In three cases (30 June 2009, 1 July 2009, 11 September 2013), the precipitation amounts decrease systematically with increasing CCN. On 11 September 2011, the impact of different CCN concentrations is negligible. The remaining two days show a tendency towards more pre-

5 precipitation with higher CCN concentrations. This demonstrates the large uncertainties arising from the nonlinear character of the microphysics and the ~~dependance~~ dependence of aerosol–cloud interactions on environmental conditions and cloud types. An important finding is the fact that a heterogeneous CCN distribution (VAR) with a mean concentration corresponding that of the reference run (CON), can yield to precipitation deviations ranging in the same order of magnitude than changing the total
5 CCN concentration.

Besides the integrated rain amounts, the timing of precipitation is also an important parameter for quantitative precipitation forecasting. From the precipitation rates given in Fig. 5, we see that the timing of precipitation is, at least for the domain average, not sensitive to the perturbations examined in this study. The days with weak synoptic forcing exhibit a typical summertime diurnal cycle with convection initiation around noon and largest rain rates in the afternoon. Some weaker showers
10 exist also in the early morning hours, most probably related to model spin-up effects. In contrast, strong forcing days also show significant precipitation amounts during nighttime. Based on the time evolution, we conclude that the different rain amounts of our sensitivity runs are mainly due to differences in rain intensity assuming that the number of simulated cells or their sizes do not differ substantially. The largest spread in precipitation rate agrees well with the largest deviations of the accumulated precipitation in Fig. 4.

15 To further address deviations of the sensitivity runs from the reference run, we now analyze the root mean square error (RMSE) of total precipitation and its temporal evolution (Fig. 6). It can be seen that the increase of errors is generally largest for the times with maximum precipitation rates. For the weak forcing cases (Fig. 6 (a)-(c)), orography and aerosol modifications lead to larger RMSE values already for smaller rain rates in the early morning hours than the soil moisture runs. Interestingly, the soil moisture runs show a steeper increase once convection is initiated around 10:00–11:00 UTC. In agreement with recent
20 findings of Baur et al. (2018), this indicates that heterogeneous soil moisture perturbations mainly influence the convection initiation via secondary dynamical effects (like thermally induced circulations), whereas CCN and orography variations induce variability already from the beginning of the simulation. Overall, the errors are largest in the soil moisture and orography runs and smallest in the aerosol runs. This is also true for the cases with strong synoptic forcing (Fig. 6 (d)-(f)). However, there is no distinct temporal delay of the soil moisture runs indicating that its influence on precipitation initiation is weaker than on
25 days with weak synoptic forcing. We also find that the spread at the end of the simulation of the aerosol runs is always higher for strong than for weak synoptic forcing, which points to a larger role of CCN concentrations in this weather regime. The same holds true for the soil moisture runs which also possess the largest spreads of all sensitivities studied here. On average, the orography runs have a similar spread in both weather regimes.

3.2 Object-based rainfall characterization using the *SAL* technique

30 To better quantify the precipitation characteristics ~~of our ensemble~~ in our model runs, we use the object-based structure-amplitude-location (*SAL*) method developed by Wernli et al. (2008). The *SAL* method objectively determines the characteristics of the precipitation fields by comparing the structure *S*, amplitude *A*, and location *L* of the simulated precipitation usually to observations for verification purposes. In this study, we apply this technique to compare the reference simulation with the rest of the ~~ensembles~~ sensitivity runs, similar as in the study of Henneberg et al. (2018). The amplitude component *A*

represents the normalized differences (between -2 and $+2$) of the domain-averaged precipitation values and hence gives an indication whether more ($A > 0$) or less ($A < 0$) precipitation is simulated compared to observations or a reference simulation, thereby neglecting spatial patterns. The location component L comprises two measures. First, the normalized distance between the center of mass between the objects in the reference and sensitivity simulation and second, the average distance between the center of mass of the individual objects and the total precipitation field. L can range between 0 and 1, and the smaller the value, the better the agreement. The structure component S compares the volume of the normalized precipitation objects by capturing their size and shape. For this, the weighted means of the normalized volume of the precipitation objects are calculated. ~~Small values indicate too small~~ Negative values indicate smaller or too peaked precipitation objects compared to the reference run and ~~large positive~~ values mean the opposite. For a detailed mathematical description and examples, we refer to the paper of Wernli et al. (2008). Usually, 24 h accumulated precipitation fields are compared with this technique with the drawback that the time evolution is not considered and errors can cancel out during the day. For this reason, we compute S , A and L values for hourly model data. These values are then averaged only for the periods with sufficient high rain intensity to avoid large SAL -errors during very weak precipitation. As the S and L components both require individual precipitation objects, we apply a threshold of 1 mm h^{-1} .

The result of this analysis is depicted in Fig. 7. The times not considered for the daily averages are marked by gray areas in Fig. 8. The mean SAL diagram shows generally smaller SAL values ~~as than~~ in other studies (e.g., Barrett et al., 2015). This is because we compare a reference simulation to sensitivity runs and not to observations. In particular, the location component shows small values indicating that our perturbations do not possess a large impact on the location of precipitation. The days with weak synoptic forcing generally have a larger variation in their SAL components as the days with strong synoptic forcing.

The results of the SAL -diagrams show most variations in the structure component (Fig. 7). Averaged for all days, the aerosol simulations have the highest absolute S value (0.15) compared to the soil moisture (0.11) or orography (0.08) simulations. The orography simulations are centered around zero S for strong synoptic forcing (Fig. 7d,e,f), which indicates that there is very little effect on the structure. This supports the previous findings, namely that changes in the terrain structure only impose a small effect on mean precipitation (Fig. 4). For the soil moisture simulations, the daily averaged S component is often negative.

Whereas on weak forcing days, the individual simulations show different S values, the strong forcing cases show similar S values for the random and chess board simulations. The aerosol simulations cover a wide range of S values, both for strong and weak synoptic forcing. Very prominent is the maritime simulation, which has the most negative S component of the aerosol simulations on all days. The reason is that the maximum precipitation amounts are much higher in the maritime than the other aerosol simulations. Since the structure scales with the maximum precipitation within each object, the S value is smaller in the maritime simulations than in the other aerosol simulations. The missing convection invigoration in our model, reflected by the higher rain intensities and stronger updrafts in clean conditions, was also reported by Barthlott and Hoose (2018) who stated that the model results could also be influenced by the saturation adjustment scheme to treat condensational growth. Such a scheme has been shown to enhance condensation and latent heating at lower levels, which could limit the potential for a CCN increase to increase buoyancy at mid to upper levels (Lebo et al., 2012).

The amplitude component is much smaller than the structure component, but does explain the precipitation totals well for all strong forcing days: They show an increase in precipitation compared to the reference simulation at positive A values and a decrease for negative A values (Fig. 7d,e,f). On the weak forcing days, there are simulations, in which the amplitude does not reflect the precipitation sum. On 30 June 2009 (Fig. 7a), the EXT2800 and EXT7000 simulation have negative A components, while the precipitation is enhanced compared to the reference. On 1 July 2009 (Fig. 7b) the EXT7000 and on 23 July 2013 (Fig. 7c) the EXT2800 simulations do not represent the precipitation totals well. Similarly, the soil moisture simulations show a good agreement of the A component to the precipitation totals under strong synoptic forcing. On 23 July 2013, the bias simulations show smaller absolute A values compared to the other soil moisture simulations and on 30 June 2009, the random simulations show a negative A component, while they have increased precipitation amounts compared to the reference simulation. The A component of the aerosol simulations represents the mean precipitation for weak forcing cases well, except on 30 June 2009 in the INT simulations. On strong forcing days, differences exist for example on 28 July 2013, when the A component is positive in the POL run, but precipitation is reduced compared to the reference simulation. Considering all days, the absolute A component for the orography is 0.05 and slightly higher than that of soil moisture and orography (0.03).

The location component is generally small (Fig. 7), meaning that the place where precipitation falls is not affected much by the uncertainties addressed in our study. For the orography simulations, the shift is somewhat higher only on 30 June 2009 (Fig. 7a) and 23 July 2013 (Fig. 7c), possibly because there is a stronger surface–atmosphere coupling during weak large-scale forcing. This would be in agreement with findings from the soil moisture simulations, as they also show higher L values for some of these day’s simulations. On 28 July 2013, the bias and uniform simulation have the highest change in the location (Fig. 7e). Interestingly, the chess and random simulations show small L values, despite the formation of convergence zones due to horizontal soil moisture gradients (not shown), which could affect the location. This indicates that also other mechanisms are important to trigger convection on these days. The aerosol simulations mostly alter the location of precipitation on strong forcing days. Interestingly, the L value is very similar for orography, soil moisture and aerosols (0.05) on all days. In summary, the amplitude and location are less affected than the structure. However, changes in the structure occur mainly due to changes in maximum precipitation amounts. Since the amplitude can explain some of the precipitation sums, we now analyze hourly time-series of the A component.

3.3 Factors determining the rain amount

Orography

The daily averaged amplitude component did not explain the precipitation totals for two weak forcing days, but the time series allows for a more in-depth investigation. On 30 June 2009, the EXT7000 simulation has the highest amplitude between 12:00 UTC and 20:00 UTC, the EXT2800 simulation is slightly smaller, and the EXT1000 simulation shows the smallest values (Fig. 8a). This result fits well to the precipitation totals. After 20:00 UTC when the domain-averaged precipitation rate is below $0.02 \text{ mm} (30 \text{ min}^{-1})$, the amplitude becomes negative in all simulations, which can explain the daily mean amplitude.

Similarly, on 23 July 2013 the EXT1000 simulation (Fig. 8c), has positive A values between 11:00–16:00 UTC. The values become very small after 20:00 UTC, which results in a negative time-averaged A value in Fig. 4.

The fact that smoothing the orography can enhance precipitation amounts despite a weaker trigger mechanism by reduced low-level wind convergence is surprising. In the following we therefore investigate why the orography simulations show more precipitation than the reference simulation on three days (Fig. 4) by analyzing the processes underlying these sensitivities. On 28 July 2013, the deviation is small and we will restrict the analysis to 30 June 2009, as the patterns resemble those for 1 July 2009. Before 12:00 UTC the low-level wind convergence is weaker the smoother the surface is (Fig. 9b). We use the velocity

$$w_{\text{diff}} = w_{\text{max}} - w_{\text{CIN}},$$

which describes the difference between the simulated maximum vertical velocity (w_{max}) below the level of free convection and the required updraft to overcome convective inhibition ($w_{\text{CIN}} = \sqrt{2 \times \text{CIN}}$) to investigate whether convection can be initiated or not. If w_{diff} is positive, the updrafts are strong enough to transport air parcels to their respective level of free convection, convection will be initiated and CAPE released (Trier, 2003). The combined measure of gridpoints with $w_{\text{diff}} > 0 \text{ m s}^{-1}$ and $\text{CAPE} > 600 \text{ J kg}^{-1}$ (Fig. 9c) confirms our expectations, namely that it is more difficult to initiate deep convection with smoother surface due to reduced low-level wind convergence. As a consequence, there is a short delay in precipitation initiation and hence CAPE has more time to build up through solar heating (Fig. 9a), **especially-only** in the EXT2800 and EXT7000 simulations. Despite less favorable conditions, low-level wind convergence is still strong enough to trigger convection in these simulations. Because the static instability is higher, convection is stronger with more precipitation than in the reference simulation. The precipitation difference between the reference and the EXT1000 simulation is only minor, and so are differences in CAPE, possibly because the difference in terrain height is also marginal. **We must further evaluate if the smoothing of terrain features, leading to somewhat lower terrain heights, has any implications on the precipitable water content. The analysis of the temporal evolution of precipitable water reveals that only marginal changes with respect to the reference run occur (relative deviations ranging between -0.61% and +0.28%), which indicates a negligible effect.**

Soil moisture

The A component is important to quantify the precipitation totals. However, on 30 June 2009 the daily-averaged A component does not follow the precipitation totals in the simulations with random patterns. As can be seen in Fig. 8g, their values become rather small after 18:00 UTC, which mainly determines the daily average in Fig. 7. On 1 July 2009, the precipitation was reduced in the SM_075 simulation compared to the reference case, but the daily-averaged amplitude was close to zero. Similarly, on 23 July 2013, the bias simulations showed a strong positive soil moisture–precipitation feedback but the daily-averaged sign in A was similar as for the random simulations. We will investigate the patterns for 23 July 2013 as they are most pronounced. Interestingly, the time series of the A component shows changes in sign for all simulations (Fig. 8i). While the wet run (SM_125) shows negative values around noon, all other runs reveal positive values. Around 15:00 UTC, there is a change in sign for all model runs. Thus, the daily averaged A value is not representative. The temporal evolution of the A component fits relatively well to the temporal evolution of precipitation and can be explained by convection-related

parameters (Fig. 10). The soil moisture controls the partitioning of the available energy at the surface (net radiation minus soil heat flux) into latent and sensible heat. During daytime, the Bowen ratio β (i.e. the ratio between the sensible and latent heat flux) increases to values larger than 1 in the SM_075 simulation as a result of the dominating sensible heat flux. This enhances the near-surface temperature (not shown) and turbulence in the boundary layer, which will lead to an increased low-level wind convergence compared to a simulation with enhanced soil moisture. ~~Therefore, As a result of the weaker latent heat flux, the lifting condensation level is higher (not shown) and CAPE is reduced compared to the SM_125 simulation. This is represented by a positive A (Fig. 8i). The enhanced low-level wind convergence in the~~ SM_075 simulation ~~is connected with stronger updrafts, thereby triggers convection leading to more precipitation than in the reference run. This can be explained by the stronger lifting from low-level wind convergence and the fact that there is still enough CAPE in the atmosphere to allow for deep convection to develop. This leads to higher rain intensities between 10:00–14:00 UTC compared to the reference or SM_125 simulation –which are also represented by a positive A (Fig. 8i).~~ On the other hand, CAPE can build up higher in the SM_125 simulation, and this leads to an enhancement of precipitation compared to the reference simulation after 15:00 UTC. The higher precipitation rate compared to the reference simulation is reflected in the increase of the A value (Fig. 8i) and leads even to a positive A component in the SM_125 simulation after 18:00 UTC. The random and chess board simulations show increasing values until 12:00 UTC, remain positive until 15:00 UTC and decrease afterwards to negative values. These mass process rates have been integrated vertically and averaged over the domain. In general, these simulations show similar values for the Bowen ratio and CAPE, and only minor differences in the low-level wind convergence compared to the reference run. This leads to small differences in precipitation, which results in differences in the amplitude.

The simulations for days with strong synoptic forcing show less variations in the A component than do the days with weak forcing. On 11 September 2011 and 2013, the A component shows only small differences in all model runs. Only on 28 July 2013, larger deviations from 0 exist for the soil moisture and aerosol uncertainties (Fig. 8k,q). The precipitation totals are in agreement with the evolution of the amplitude component on all days. As has been noted earlier, this day is the only one without a systematic soil moisture–precipitation relationship. Before 15:30 UTC, both the dry and the wet simulations mostly reveal higher amplitude components ~~as~~ than the reference run. Later on, both time series become negative, resulting in an overall precipitation reduction compared to the reference run. In general, the surface fluxes are smaller on strong forcing days and hence the surface–atmosphere coupling is weaker. Changes that do occur mainly result from modifications in the total precipitable water as a result of small changes of evaporation (not shown).

Aerosols

On 30 June 2009 (Fig. 8m) between 9:00–19:00 UTC, on 1 July 2009 (Fig. 8n) between 9:00–14:00 UTC and 11 September 2013 (Fig. 8r), there is a tendency for decreasing amplitude from maritime to continental conditions, and so does the precipitation amount (Fig. 4). One common characteristic for these days is that the domain-averaged updraft velocities within the clouds (regions where the integrated cloud and rain water path is larger than 0.01 mg m^{-2}), is always smaller than 0.25 m s^{-1} (not shown).

On 11 September 2011 there is a weak decrease in the amplitude component after 12:00 UTC from polluted to maritime conditions (Fig. 8p). On 28 July 2013, the amplitude is highest in the polluted and lowest in the maritime simulation (Fig. 8j). On 23 July 2013, the order changes at 15:00 UTC (Fig. 8o) and also the precipitation sums are less systematic. On these three days, the updraft velocities within clouds are always higher than 0.38 m s^{-1} and therefore higher as in the three cases described above. The different vertical velocities, and thus the environmental conditions then affect the dominant cloud microphysical pathways, which are now analyzed using microphysical process rates. The warm-phase processes are autoconversion (collision of cloud droplets) and accretion (rain droplets collecting cloud droplets), the dominant cold-phase processes are vapor deposition on ice crystals and riming (collision of a droplet and an ice crystal). In general, cold-rain processes dominate in all our simulations as the ratio of warm- to cold-rain processes is always less than one (Fig. 11). On 28 July 2013 and On 11 September 2011 and 28 July 2013, cold processes are much more important than warm processes as indicated by the small ratio of warm- to cold-rain processes, due to the stronger lifting. On 23 July 2013 the ratio is higher, possibly because we find a regime change during the high intensity period. For these three days, the higher vertical velocity leads to a pronounced transport of cloud droplets towards higher altitudes, especially for polluted conditions, when cloud droplets are smaller (not shown) and hence persist longer within the clouds than it is the case for maritime conditions. As mentioned earlier, we do not observe stronger updrafts in polluted conditions, and thus no convection invigoration as hypothesized by Rosenfeld et al. (2008). Instead, when the cloud particles grow via the cold phase and then precipitate, they have bigger sizes than the droplets in the maritime conditions (not shown), and are thus less susceptible to evaporation below cloud base which leads to higher precipitation amounts with increasing CCN.

On the other hand, warm phase processes are almost similarly important as cold phase processes on 30 June and 1 July 2009, due to the weaker updrafts and even on 11 September 2013, the ratio is always above 0.5. On these days, the suppression of collision-coalescence with increasing CCN has larger effects on the precipitation amounts (as cold-phase processes and melting contribute relatively less) and hence a reduction in precipitation towards more polluted conditions. For a more detailed analysis of hydrometeor profiles and microphysical process rates, we refer to Schneider (2018).

4 Summary and conclusions

The purpose of this study was to investigate the relative contribution of orography, soil moisture and aerosols on the predictability of deep convection. To this end, we performed 500 m grid length numerical simulations with the COSMO model for six real-case events over Germany classified into weak and strong large-scale forcing. The sensitivities comprise smoothing the terrain, systematic changes in the initial soil moisture field, and different homogeneous and spatially heterogeneous CCN concentrations.

In general, weak forcing days show smaller precipitation amounts than strong forcing days, but a higher precipitation susceptibility (-12 to $+15\%$) to the applied changes than strong forcing days (-9 to $+7\%$). We find that uncertainties in soil moisture and CCN concentrations contribute the most to the ensemble spread spread in our sensitivity runs. The modifications in soil moisture have the strongest impact on two weak forcing and one strong forcing day. For the majority of the analyzed

cases, the model produces a positive soil moisture–precipitation feedback in agreement with e.g., Findell and Eltahir (2003) or Cioni and Hohenegger (2017). Different patches of dry and wet soils have, on average, smaller effects on the simulated precipitation amounts than the dry or wet bias experiments. We therefore conclude that ~~correct initial values are much the~~ initial soil moisture amount is more important than the spatial distribution of dry and wet patches assuming a constant spatial average.

5 The aerosol simulations have the strongest impact on one weak forcing and two strong forcing days. Furthermore, we find that an increase in CCN concentrations can either lead to an increase or decrease in precipitation, depending on the environmental conditions and different contributions of warm and cold-rain processes. In all our simulations, the contribution of cold-rain processes is higher than that of warm-rain processes. For weak updrafts, however, the relative role of the warm-phase processes is higher and a reduction in precipitation occurs with higher CCN concentrations and smaller droplets. For stronger updrafts, 10 the cold-phase processes dominate. The precipitation thus increases with increasing CCN, as bigger raindrops that occur via the cold-phase are less susceptible to low-level evaporation (Tao et al., 2007; Barthlott et al., 2017). An important finding is the fact that a heterogeneous CCN distribution with a mean concentration corresponding to that of the reference run (continental assumption), can ~~yield-lead~~ to precipitation deviations ranging in the same order of magnitude than changing the total CCN concentration. The fact that soil moisture and aerosol perturbations contribute in a similar magnitude to the precipitation totals 15 suggests that aerosols are indeed important for quantitative precipitation ~~forecast-forecasting~~ (Miltenberger et al., 2018). The smallest deviations from the reference runs occurred when introducing orography uncertainties. Surprisingly, on three days, the smoothing of terrain features lead to higher precipitation amounts. This could be attributed to a slightly increased instability compensating for the weaker triggering by low-level wind convergence. In addition, the resolution of external data is less important for strong synoptic forcing as mesoscale rising of air over mountain ridges can still be reasonably well simulated 20 without fine-scale orographical features like valleys.

To investigate amplitude, location and structure of precipitation, we compute *SAL* diagrams based on hourly precipitation fields. We find that the structure parameter is affected the most, followed by the amplitude and only small variations in the location. On average, the highest structure parameters occur in aerosol simulations (absolute mean 0.15). Changes in the structure occur mainly due to increased maximum precipitation amounts. The evolution of rain intensities was mostly well 25 correlated with the amplitude component. The location component does not vary much between the three sensitivities and the absolute value lies around 0.05. Because of this resemblance, we hypothesize that this shift is due to noise resulting from different CCN assumptions and initially small perturbations to the thermodynamics/dynamics. This is in accordance with previous findings of Schneider et al. (2018), namely that the shift in precipitation in the orography simulations resembles the patterns for artificially introduced noise. As a thorough discussion of all involved processes and feedbacks for all sensitivities 30 and cases would be exhaustive, we refer to Schneider (2018) for more details.

To increase the reliability of operational ensembles, we will probably observe a further increase in the use of ensemble methods, but this will require more effort to perturb the model (Leutbecher et al., 2017). The overall goal for these perturbations is to make them as realistic and relevant as possible. For the operational forecast, ensembles, which perturb initial conditions, boundary data and model physics, are run to account for the various uncertainties. Based on the results of this study, we suggest 35 to account for variations in soil moisture and aerosols, also because both are associated with a high measurement uncertainty

(e.g., Van Reken et al., 2003; Hauck et al., 2011). For the soil moisture perturbations, adapted ensembles could be meaningful, i.e., by perturbing different components depending on the large-scale synoptic situation. After all, we conclude that these uncertainties should be included in a full ensemble forecasting system containing other key sources of uncertainty to estimate their relative importance for longer periods.

5 *Data availability.* COSMO model output is available on request from the authors.

Author contributions. CB and CH developed the project idea, they designed the numerical experiments with LS who carried them out. [AB contributed with technical implementations to write out microphysical process rates and to use horizontal heterogeneous CCN concentrations in the COSMO model code.](#) LS conducted the analyses and all contributed to the interpretation of the results. LS wrote the first version of the paper, CB extensively edited it with contributions from CH [and AB.](#)

10 *Competing interests.* The authors declare that they have no conflict of interest.

Acknowledgements. The research leading to these results has been done within the subproject “B3: Relative impact of surface and aerosol heterogeneities on the initiation of deep convection” of the Transregional Collaborative Research Center SFB/TRR 165 “Waves to Weather” funded by the German Research Foundation (DFG). The authors wish to thank the Deutscher Wetterdienst (DWD) for providing the COSMO model code and the initial and boundary data. This work was performed on the computational resource ForHLR I and II funded by the

15 Ministry of Science, Research and the Arts Baden-Württemberg and DFG (“Deutsche Forschungsgemeinschaft”). [Furthermore, we wish to thank Dr. Hassan Beydoun \(KIT\) for fruitful discussions.](#)

References

- Altaratz, O., Koren, I., Remer, L., and Hirsch, E.: Review: Cloud invigoration by aerosols: Coupling between microphysics and dynamics, *Atmos. Res.*, 140-141, 38 – 60, 2014.
- Baldauf, M., Seifert, A., Förstner, J., Majewski, D., and Raschendorfer, M.: Operational convective-scale numerical weather prediction with
5 the COSMO model: description and sensitivities, *Mon. Wea. Rev.*, 139, 3887–3905, <https://doi.org/10.1175/MWR-D-10-05013.1>, 2011.
- Barrett, A. I., Gray, S. L., Kirshbaum, D. J., Roberts, N. M., Schultz, D. M., and Fairman, J. G.: Synoptic versus orographic control on stationary convective banding, *Q. J. R. Meteorol. Soc.*, 141, 1101–1113, <https://doi.org/10.1002/qj.2409>, 2015.
- Barthlott, C. and Hoose, C.: Spatial and temporal variability of clouds and precipitation over Germany: multiscale simulations across the "gray zone", *Atmos. Chem. Phys.*, 15, 12 361–12 384, <https://doi.org/10.5194/acp-15-12361-2015>, 2015.
- 10 Barthlott, C. and Hoose, C.: Aerosol effects on clouds and precipitation over central Europe in different weather regimes, *J. Atmos. Sci.*, 75, 4247–4264, <https://doi.org/10.1175/JAS-D-18-0110.1>, 2018.
- Barthlott, C. and Kalthoff, N.: A Numerical Sensitivity Study on the Impact of Soil Moisture on Convection-related Parameters and Convective Precipitation over Complex Terrain, *jas*, 68, 2971–2987, <https://doi.org/10.1175/JAS-D-11-027.1>", 2011.
- Barthlott, C., Adler, B., Kalthoff, N., Handwerker, J., Kohler, M., and Wieser, A.: The role of Corsica in initiating nocturnal offshore
15 convection, *Q. J. R. Meteorol. Soc.*, 142, 222–237, <https://doi.org/10.1002/qj.2415>, 2016.
- Barthlott, C., Mühr, B., and Hoose, C.: Sensitivity of the 2014 Pentecost storms over Germany to different model grids and microphysics schemes, *Q. J. R. Meteorol. Soc.*, 143, 1485–1503, <https://doi.org/10.1002/qj.3019>, 2017.
- Baur, F., Keil, C., and Craig, G.: Soil Moisture - Precipitation Coupling over Central Europe: Interactions between surface anomalies at different scales and its dynamical implication, *Q. J. R. Meteorol. Soc.*, 144, 2863–2875, <https://doi.org/10.1002/qj.3415>, 2018.
- 20 Berner, J., Achatz, U., Batté, L., Bengtsson, L., Cámara, A. d. l., Christensen, H. M., Colangeli, M., Coleman, D. R. B., Crommelin, D., Dolaptchiev, S. I., Franzke, C. L. E., Friederichs, P., Imkeller, P., Järvinen, H., Juricke, S., Kitsios, V., Lott, F., Lucarini, V., Mahajan, S., Palmer, T. N., Penland, C., Sakradzija, M., von Storch, J.-S., Weisheimer, A., Weniger, M., Williams, P. D., and Yano, J.-I.: Stochastic Parameterization: Toward a New View of Weather and Climate Models, *Bull. Amer. Meteor. Soc.*, 98, 565–588, <https://doi.org/10.1175/BAMS-D-15-00268.1>, 2017.
- 25 Bouttier, F. and Raynaud, L.: Clustering and selection of boundary conditions for limited area ensemble prediction, *Q. J. R. Meteorol. Soc.*, 144, 2381–2391, <https://doi.org/10.1002/qj.3304>, 2018.
- Cioni, G. and Hohenegger, C.: Effect of Soil Moisture on Diurnal Convection and Precipitation in Large-Eddy Simulations, *J. Hydrometeor.*, 18, 1885–1903, 2017.
- Clark, P., Roberts, N., Lean, H., Ballard, S. P., and Charlton-Perez, C.: Convection-permitting models: a step-change in rainfall forecasting,
30 *Meteorological Applications*, 23, 165–181, 2016.
- Courault, D., Drobinski, P., Brunet, Y., Lacarre, P., and Talbot, C.: Impact of surface heterogeneity on a buoyancy-driven convective boundary layer in light winds, *Boundary-Layer Meteorol.*, 124, 383–403, <https://doi.org/10.1007/s10546-007-9172-y>, 2007.
- Doms, G., Förstner, J., Heise, E., Herzog, H.-J., Mironov, D., Raschendorfer, M., Reinhardt, T., Ritter, B., Schrodin, R., Schulz, J.-P., and Vogel, G.: A description of the nonhydrostatic regional COSMO model, Part II: Physical Parameterization, 2011.
- 35 Findell, K. L. and Eltahir, E. A. B.: Atmospheric controls on soil moisture-boundary layer interactions. Part I: Framework development, *J. Hydrometeor.*, 4, 552–569, 2003.

- Froidevaux, P., Schlemmer, L., Schmidli, J., Langhans, W., and Schär, C.: Influence of the Background Wind on the Local Soil Moisture–Precipitation Feedback, *J. Atmos. Sci.*, 71, 782–799, <https://doi.org/10.1175/JAS-D-13-0180.1>, 2014.
- Groenemeijer, P., Barthlott, C., Behrendt, A., Corsmeier, U., Handwerker, J., Kohler, M., Kottmeier, C., Mahlke, H., Pal, S., Radlach, M., Trentmann, J., Wieser, A., and Wulfmeyer, V.: Observations of kinematics and thermodynamic structure surrounding a convective storm cluster over a low mountain range, *Mon. Wea. Rev.*, 137, 585–602, <https://doi.org/10.1175/2008MWR2562.1>, 2009.
- Guillot, B. P., Orlowsky, B., Miralles, D., Teuling, A. J., Blanken, P. D., Buchmann, N., Ciais, P., Ek, M., Findell, K. L., Gentine, P., Lintner, B. R., Scott, R. L., Van den Hurk, B., and I. Seneviratne, S.: Land-surface controls on afternoon precipitation diagnosed from observational data: uncertainties and confounding factors, *Atmos. Chem. Phys.*, 14, 8343–8367, <https://doi.org/10.5194/acp-14-8343-2014>, 2014.
- Hande, L. B., Engler, C., Hoose, C., and Tegen, I.: Parameterising Cloud Condensation Nuclei concentrations during HOPE, *Atmos. Chem. Phys.*, 16, 12 059–12 079, <https://doi.org/10.5194/acp-2016-357>, 2016.
- Hauck, C., Barthlott, C., Krauss, L., and Kalthoff, N.: Soil moisture variability and its influence on convective precipitation over complex terrain, *Q. J. R. Meteorol. Soc.*, 137, 42–56, <https://doi.org/10.1002/qj.766>, 2011.
- Henneberg, O., Ament, F., and Grützun, V.: Assessing the uncertainty of soil moisture impacts on convective precipitation using a new ensemble approach, *Atmos. Chem. Phys.*, 18, 6413–6425, <https://doi.org/10.5194/acp-18-6413-2018>, 2018.
- Hohenegger, C., Brockhaus, P., Bretherton, C. S., and Schär, C.: The Soil Moisture–Precipitation Feedback in Simulations with Explicit and Parameterized Convection, *J. Climate*, 22, 5003–5020, 2009.
- Imamovic, A., Schlemmer, L., and Schär, C.: Collective Impacts of Orography and Soil Moisture on the Soil Moisture–Precipitation Feedback, *Geophys. Res. Lett.*, 44, 11,682–11,691, <https://doi.org/10.1002/2017GL075657>, 2017.
- Khain, A. P., BenMoshe, N., and Pokrovsky, A.: Factors Determining the Impact of Aerosols on Surface Precipitation from Clouds: An Attempt at Classification, *J. Atmos. Sci.*, 65, 1721–1748, <https://doi.org/10.1175/2007JAS2515.1>, 2008.
- Kirshbaum, D. J., Adler, B., Kalthoff, N., Barthlott, C., and Serafin, S.: Moist Orographic Convection: Physical Mechanisms and Links to Surface-Exchange Processes, *Atmosphere*, 9, 80, <https://doi.org/10.3390/atmos9030080>, 2018.
- Kühnlein, C., Keil, C., Craig, G. C., and Gebhardt, C.: The impact of downscaled initial condition perturbations on convective-scale ensemble forecasts of precipitation, *Q. J. R. Meteorol. Soc.*, 140, 1552–1562, 2014.
- Lebo, Z. J., Morrison, H., and Seinfeld, J. H.: Are simulated aerosol-induced effects on deep convective clouds strongly dependent on saturation adjustment?, *Atmos. Chem. Phys.*, 12, 9941–9964, <https://doi.org/10.5194/acp-12-9941-2012>, 2012.
- Leutbecher, M., Lock, S.-J., Ollinaho, P., Lang, S. T. K., Balsamo, G., Bechtold, P., Bonavita, M., Christensen, H. M., Diamantakis, M., Dutra, E., English, S., Fisher, M., Forbes, R. M., Goddard, J., Thomas, H., J., H. R., Stephan, J., Heather, L., Dave, M., Linus, M., Sylvie, M., Sebastien, M., Sandu, I., Smolarkiewicz, P. K., Subramanian, A., Vitart, F., Wedi, N., and Weisheimer, A.: Stochastic representations of model uncertainties at ECMWF: state of the art and future vision, *Q. J. R. Meteorol. Soc.*, 143, 2315–2339, <https://doi.org/10.1002/qj.3094>, 2017.
- Mellor, G. L. and Yamada, T.: A hierarchy of turbulence closure models for planetary boundary layers, *J. Atmos. Sci.*, 31, 1791–1806, 1974.
- Miltenberger, A. K., Field, P. R., Hill, A. A., Rosenberg, P., Shipway, B. J., and Wilkinson, J. M.: Aerosol–cloud interactions in mixed-phase convective clouds – Part 1: Meteorological ensemble, *Atmos. Chem. Phys.*, 18, 10 593–10 613, <https://doi.org/10.5194/acp-18-10593-2018>, 2018.
- Mittermaier, M. P.: A Strategy for Verifying Near-Convection-Resolving Model Forecasts at Observing Sites, *Wea. and Forec.*, 29, 185–204, 2014.

- Noppel, H., Blahak, U., Seifert, A., and Beheng, K. D.: Simulations of a hailstorm and the impact of CCN using an advanced two-moment cloud microphysical scheme, *Atmos. Res.*, 96, 286–301, <https://doi.org/10.1016/j.atmosres.2009.09.008>, 2010.
- Pan, Z., Takle, E., Segal, M., and Turner, R.: Influences of model parameterization schemes on the response of rainfall to soil moisture in the central United States, *Mon. Wea. Rev.*, 124, 1786–1802, 1996.
- 5 Phillips, V. T. J., DeMott, P. J., and Andronache, C.: An empirical parameterization of heterogeneous ice nucleation for multiple chemical species of aerosol, *J. Atmos. Sci.*, 65, 2757–2783, 2008.
- Picard, L. and Mass, C.: The Sensitivity of Orographic Precipitation to Flow Direction: An Idealized Modeling Approach, *J. Hydrometeorol.*, 18, 1673–1688, <https://doi.org/10.1175/JHM-D-16-0209.1>, 2017.
- Richard, E., Chaboureaud, J. P., Flamant, C., Champollion, C., Hagen, M., Schmidt, K., Kiemle, C., Corsmeier, U., Barthlott, C., and Di
10 Girolamo, P.: Forecasting summer convection over the Black Forest: a case study from the Convective and Orographically-induced Precipitation Study (COPS) experiment, *Q. J. R. Meteorol. Soc.*, 137 (S1), 101–117, <https://doi.org/10.1002/qj.710>, 2011.
- Rihani, J. F., Chow, F. K., and Maxwell, R. M.: Isolating effects of terrain and soil moisture heterogeneity on the atmospheric boundary layer: Idealized simulations to diagnose land-atmosphere feedbacks, *Journal of Advances in Modeling Earth Systems*, 7, 915–937, <https://doi.org/10.1002/2014MS000371>, 2015.
- 15 Rosenfeld, D., Lohmann, U., Raga, G. B., O’Dowd, C. D., Kulmala, M., Fuzzi, S., Reissell, A., and Andreae, M. O.: Flood or Drought: How Do Aerosols Affect Precipitation?, *Science*, 321, 1309–1313, <https://doi.org/10.1126/science.1160606>, 2008.
- Rotunno, R. and Ferretti, R.: Mechanisms of intense Alpine rainfall, *J. Atmos. Sci.*, 58, 1732–1749, 2001.
- Rotunno, R. and Houze, R. A.: Lessons on orographic precipitation from the Mesoscale Alpine Programme, *Q. J. R. Meteorol. Soc.*, 133, 811–830, <https://doi.org/10.1002/qj.67>, 2007.
- 20 Santanello, J. A., Dirmeyer, P. A., Ferguson, C. R., Findell, K. L., Tawfik, A. B., Berg, A., Ek, M., Gentine, P., Guillod, B. P., van Heerwaarden, C., Roundy, J., and Wulfmeyer, V.: Land-Atmosphere Interactions: The LoCo Perspective, *Bull. Amer. Meteor. Soc.*, 99, 1253–1272, <https://doi.org/10.1175/BAMS-D-17-0001.1>, 2018.
- Schär, C., Lüthi, D., Beyerle, U., and Heise, E.: The soil-precipitation feedback: A process study with a regional climate model, *J. Climate*, 12, 722–741, 1999.
- 25 Schättler, U.: A description of the nonhydrostatic regional COSMO-model, Part V: Preprocessing: Initial and Boundary Data for the COSMO-Model, 2016.
- Schättler, U., Doms, G., and Schraff, C.: A description of the nonhydrostatic regional COSMO-model, Part VII: User’s Guide, 2016.
- Schneider, L.: Relative impact of surface and aerosol heterogeneities on deep convection, Ph.D. thesis, Institute of Meteorology and Climate Research (IMK-TRO), Karlsruhe Institute of Technology (KIT), Germany, 124 pp, <https://doi.org/10.5445/IR/1000088510>, 2018.
- 30 Schneider, L., Barthlott, C., Barrett, A. I., and Hoose, C.: The precipitation response to variable terrain forcing over low mountain ranges in different weather regimes, *Q. J. R. Meteorol. Soc.*, 144, 970–989, <https://doi.org/10.1002/qj.3250>, 2018.
- Schumacher, R. S., Schultz, D. M., and Knox, J. A.: Influence of Terrain Resolution on Banded Convection in the Lee of the Rocky Mountains, *Mon. Wea. Rev.*, 143, 1399–1416, <https://doi.org/10.1175/MWR-D-14-00255.1>, 2015.
- Seifert, A. and Beheng, K. D.: A two-moment cloud microphysics parameterization for mixed-phase clouds. Part I: Model description,
35 *Meteorol. Atmos. Phys.*, 92, 45–66, 2006.
- Seifert, A., Köhler, C., and Beheng, K. D.: Aerosol-cloud-precipitation effects over Germany as simulated by a convective-scale numerical weather prediction model, *Atmos. Chem. Phys.*, 12, 709–725, 2012.

- Seneviratne, S. I., Corti, T., Davin, E. L., Hirschi, M., Jaeger, E. B., Lehner, I., Orlowsky, B., and Teuling, A. J.: Investigating soil moisture-climate interactions in a changing climate: A review, *Earth-Science Reviews*, 99, 125 – 161, <https://doi.org/https://doi.org/10.1016/j.earscirev.2010.02.004>, 2010.
- 5 Tao, W.-K., Li, X., Khain, A., Matsui, T., Lang, S., and Simpson, J.: Role of atmospheric aerosol concentration on deep convective precipitation: Cloud-resolving model simulations, *J. Geophys. Res.: Atmospheres*, 112, 2007.
- Taylor, C. M., de Jeu, R. A. M., Guichard, F., Harris, P. P., and Dorigo, W. A.: Afternoon rain more likely over drier soils, *Nature*, 489, 423–426, 2012.
- Theunert, F. and Seifert, A.: Simulation Studies of Shallow Convection with the Convection-Resolving Version of DWD Lokal-Modell, Available online at <http://www.cosmo-model.org> [Accessed on 31 May 2019], 2006.
- 10 Tiedtke, M.: A comprehensive mass flux scheme for cumulus parameterization in large-scale models, *Mon. Wea. Rev.*, 117, 1779–1800, 1989.
- Trier, S. B.: Convective storms - convective initiation, In: *Encyclopedia of atmospheric sciences*, Vol 2. [Holton JR, Curry JA, Pyle JA (eds)], Academic Press, London., 2003.
- van den Heever, S. C., Stephens, G. L., and Wood, N. B.: Aerosol indirect effects on tropical convection characteristics under conditions of radiative-convective equilibrium, *J. Atmos. Sci.*, 68, 699–718, 2011.
- 15 Van Reken, T. M., Rissman, T. A., Roberts, G. C., Varutbangkul, V., Jonsson, H. H., Flagan, R. C., and Seinfeld, J. H.: Toward aerosol/cloud condensation nuclei (CCN) closure during CRYSTAL-FACE, *J. Geophys. Res.: Atmospheres*, 108, 2003.
- Wernli, H., Paulat, M., Hagen, M., and Frei, C.: SAL-A Novel Quality Measure for the Verification of Quantitative Precipitation Forecasts, *Mon. Wea. Rev.*, 136, 4470–4487, <https://doi.org/10.1175/2008MWR2415.1>, 2008.
- 20 Wicker, L. J. and Skamarock, W. C.: Time-splitting methods for elastic models using forward time schemes, *Mon. Wea. Rev.*, 130, 2088–2097, 2002.




Figure 1. Reference orography at 500 m grid spacing (a) and interpolated orography from 1 km (b), 2.8 km (c) and 7 km (d) to the model grid. The black rectangle depicts the 500 m simulation domain.




Figure 2. Relative water content of the reference field (REF, a), the simulations with small (SM_RS, b) and medium (SM_RM, c) random structures, and chess board structures with grid length of 10 km (SM_10k, d), 56 km (SM_56k, e) and 112 km (SM_112k, f).




Figure 3. 24 h precipitation amount of 500 m grid length reference run in mm for the six days of investigation: (a) 30 June 2009; (b) 1 July 2009; (c) 23 July 2013; (d) 11 September 2011; (e) 28 July 2013; (f) 11 September 2013. Figure adapted from Fig. 5 in Schneider et al. (2018).




Figure 4. 24 h domain-averaged precipitation (a) and deviation from the respective reference run (b) for the six days of investigation. The symbols denote the precipitation deviation and the height of the bar shows the distance between minimum and maximum mean precipitation for each set of sensitivities.




Figure 5. Domain-averaged precipitation rates for the six days of investigation. The color-coded areas represent the spread, i.e. the maximum and minimum mean precipitation for each set of sensitivities.




Figure 6. Root mean square error (RMSE) for precipitation of the sensitivity runs compared to the reference run. Thick lines indicate the mean and color-coded areas the range between the minimum and maximum RMSE.




Figure 7. Mean SAL diagram showing the structure, amplitude, and location component for the six days of investigation averaged from hourly rainfall amounts. The more the values deviate from 0, the larger is the deviation from the respective reference run. An identical prediction would have values of 0 for each component. Note the different axes for A and S .




Figure 8. Time series of hourly computed A values for the simulations with modified orography (a)–(f), soil moisture (g)–(l) and aerosols (m)–(r) for the six days of investigation. Gray shaded areas are excluded from the computation of daily mean values in Fig. 7.




Figure 9. Temporal evolution of CAPE, 10 m wind convergence and number of points with $w_{\text{diff}} > 0 \text{ m s}^{-1}$ and $\text{CAPE} > 600 \text{ J kg}^{-1}$ on 30 June 2009 in the orography sensitivity experiments.




Figure 10. Temporal evolution of mean precipitation rate, Bowen ratio, CAPE and 10-m wind convergence on 23 July 2013 in the soil moisture sensitivity experiments.




Figure 11. Ratio between warm (autoconversion and accretion) and cold (vapor deposition and riming) rain processes as a function of the CCN concentration.